



Langone Medical Center

DEBRIS REMOVAL REQUIREMENTS

All construction areas and affected adjacent areas must be left broom clean at the end of each day. All debris must be taken down to the Loading Dock before the end of the work day. The containers must be covered and not overfilled to the point where there is a possibility of any contents spilling out as they pass through the hospital, the elevators or as they sit in the Loading Dock area. All debris containers must be empties and brought back to the construction site by 9:00 AM the next morning.